

Restoration Contractor Estimate

Claim ID	PROP-B2B-2026-0417
Insured	Nordhafen Precision Parts GmbH
Document type	Restoration estimate
Issued by	SiteDry Industrial Restoration GmbH
Document date	17 May 2026
Loss location	Hafenstrasse 18, Building B, 30179 Hannover, Germany

Estimate summary

Field	Entry
Contractor	SiteDry Industrial Restoration GmbH
Estimate number	SD-2605-114-NH
Inspection dates	13-16 May 2026
Scope basis	Emergency mitigation, smoke cleaning, water extraction, drying, selective demolition, deodorization, and reinstatement coordination
Total estimated net amount	EUR 312,450.00 excluding VAT
Exclusions	Structural roof repairs, replacement CNC electronics, stock disposal fees beyond two containers, hazardous waste surcharge if required

Cost breakdown

Line	Description	Net amount	Coverage note
1	Emergency attendance, site safety, temporary power, containment	EUR 24,800	Likely mitigation / debris removal.
2	Water extraction and drying equipment for loading bay and packing floor	EUR 36,700	Includes 21-day hire; actual duration to be checked.
3	Smoke cleaning of CNC hall surfaces, racking, tools, cable trays	EUR 78,500	May overlap with machinery cleaning quotes.
4	Selective demolition of damaged internal partitions and ceiling panels	EUR 49,900	Ownership split required.
5	Mezzanine office cleaning and server-cabinet decontamination	EUR 31,250	Equipment specialist required for electronics.
6	Replacement of charging bench area finishes and fire-rated doors	EUR 64,300	Fire door may be landlord shell; verify lease.
7	Waste handling, odour treatment, final clearance testing	EUR 27,000	Salvage and waste classification pending.

Contractor assumptions

- Estimate assumes access to all production areas from 17 May 2026 and continuous power supply to drying equipment.
- Estimate assumes no asbestos, PCB, or hazardous residue in wall panels; testing not yet performed.
- Estimate prices are valid for 30 days and exclude overtime except emergency first response.
- Contractor did not distinguish insured tenant improvements from landlord shell property.

Schedule impact stated by contractor

SiteDry estimates that emergency mitigation can stabilize the premises within 10 calendar days if debris is released by the police and electrical expert. Reinstatement of partitions, fire doors, and ceiling panels is estimated at 4 to 6 additional weeks depending on material availability. The contractor states that CNC production may resume in phases before full reinstatement if air clearance is passed and temporary separation is approved.

Areas mapped by SiteDry

Area	Damage type	Proposed action
Loading bay / charging alcove	Direct fire, soot, water, damaged bench and door finish	Demolition, clean, deodorize, reinstate finishes.
Packing area	Standing sprinkler water, soaked cartons, slippery floor	Extract water, dry slab, dispose packaging.
CNC hall	Soot film and airborne particulates	HEPA vacuum, wipe-down, corrosion inhibitor.
Mezzanine office	Smoke odour and server cabinet contamination	Specialist electronics clean; replace filters.
External yard	Run-off water and debris movement	Sweeping and waste handling; no ground remediation priced.

Estimate caveat

SiteDry confirms the estimate is not a final repair specification. Costs may reduce after scope segregation or increase if hidden contamination is found. No VAT position is stated.